

KEY NOTES

1. EXISTING UNDERGROUND TANKS TO BE REMOVED, REFER TO MECHANICAL DRAWINGS.
2. REMOVE ALL EXISTING ELECTRICAL CONNECTIONS, CONDUCTORS, CONDUIT AND CONTROLS TO PUMPS AND DISPENSERS BACK TO SOURCE.
3. EXISTING WALL MOUNTED LIGHT FIXTURE TO BE REMOVED WITH ALL WIRE AND CONDUIT BACK TO SOURCE.
4. REMOVE EXISTING CONDUIT AND SEALS FROM TANK SYSTEM BACK TO SOURCE.


GENERAL NOTES

1. ALL ITEMS SCHEDULED FOR RELOCATION SHALL BE CAREFULLY REMOVED IN REVERSE OF ORIGINAL ASSEMBLY OR PLACEMENT AND BE PROTECTED UNTIL RELOCATION. THE CONTRACTOR SHALL CLEAN, REPAIR AND PROVIDE NEW MATERIALS AND APPURTENANCES AS REQUIRED TO COMPLETE INSTALLATION AND RESTORE TO GOOD WORKING ORDER. ALL RELOCATION'S SHALL BE PERFORMED BY SKILLED WORKMEN IN ACCORDANCE WITH STANDARD PRACTICE OF THE TRADES INVOLVED.
2. ITEMS SCHEDULED FOR RELOCATION REQUIRING EXTENSION OF CIRCUITRY, SHALL HAVE THEIR WIRE AND CONDUIT EXTENDED TO THE NEW LOCATION.
3. EXTENDED WIRE AND CONDUIT SHALL BE ROUTED IN SUCH A MANNER SO AS NOT TO INTERFERE WITH THE USE OR ESTHETICS OF ANY AREA IN WHICH IT IS ROUTED. THE CONTRACTOR SHALL BE RESPONSIBLE FOR RELOCATING OR MODIFYING AND RECONNECTING ANY PANELBOARDS OR OTHER ELECTRICAL EQUIPMENT ASSOCIATED WITH ITEMS BEING RELOCATED.
4. CIRCUITS WITH ONLY A PORTION OF THE LOAD REMOVED SHALL HAVE THE REMOVED LOADS ASSOCIATED CIRCUITRY REMOVED ONLY TO A POINT OR IN SUCH A MANNER THAT THE REMAINING LOAD IS ACTIVE AND IN FIRST CLASS WORKING ORDER.
5. ASSOCIATED CIRCUITRY IS DEFINED AS ALL WIRE, CONDUIT, J-BOXES, WIRING DEVICES, DEVICE BOXES, FUSES, DISCONNECT SWITCHES, ETC. ASSOCIATED WITH THE ITEM SCHEDULED FOR REMOVAL.
6. ITEMS SCHEDULED FOR REMOVAL WITH CONDUIT IN INACCESSIBLE AREAS SHALL HAVE ALL CONDUCTORS REMOVED BACK TO SOURCE AND CONDUIT SEALED OR CAPPED IN A SAFE MANNER ACCEPTABLE TO THE OWNER.
7. WHERE ITEMS SCHEDULED FOR REUSE OR RELOCATION ARE FOUND TO BE IN DAMAGED CONDITION, THE CONTRACTOR SHALL CALL THE ATTENTION OF THE OWNER TO SUCH ITEMS AND RECEIVE FURTHER INSTRUCTIONS PRIOR TO REMOVAL. ITEMS DAMAGED DURING RELOCATION SHALL BE REPAIRED OR REPLACED BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE OWNER.
8. ALL CUTTING AND PATCHING REQUIRED FOR INSTALLATION OF FACEWAYS OR EQUIPMENT SHALL BE PERFORMED BY A TRADESMAN EXPERIENCED IN THE WORK REQUIRED. ALL FINISHES SHALL MATCH EXISTING ADJACENT SURFACES.
9. ITEMS SALVAGED SHALL BE MOVED AND STORED IN A LOCATION AS DIRECTED BY THE OWNER. REFUSE MATERIALS AND ITEMS NOT TO BE SALVAGED SHALL BE REMOVED FROM THE SITE FOR DISPOSAL.
10. PROMPTLY REPAIR DAMAGE CAUSED TO ADJACENT FACILITIES BY DEMOLITION OPERATIONS AT NO COST TO THE OWNER.
11. CONTRACTOR SHALL REMOVE ANY UNUSED CONDUCTORS FROM EXISTING PANEL AND UPDATE PANELS SCHEDULE.

ELECTRICAL DEMOLITION PLAN

SCALE: 1/8" = 1'-0"

NORTH



RICHEY BLVD. FUEL TANK REPLACEMENT
PIMA COUNTY
 FACILITIES MANAGEMENT
 150 WEST CONGRESS, 5TH FL.
 TUCSON, AZ 85701

2051 W. SUNSET RD.
 SUITE NO. 101
 TUCSON, ARIZONA 85704
 TEL: (520) 293-1488
 FAX: (520) 293-6349
 WWW.M3PN.COM

ARCHITECTURE
 ENGINEERING
 CONSTRUCTION MANAGEMENT

Revisions

Description	Date

Drawn: RLA
 Checked: EBL
 Issue Date: 12-17-2010

Drawing Title
ELECTRICAL DEMOLITION PLAN

Sheet Number
ED101

M3PN 100100
 Last Update: 7.1.2011