



**PIMA COUNTY PROCUREMENT DEPARTMENT
DESIGN AND CONSTRUCTION DIVISION**
130 W. CONGRESS STREET, 3rd FLOOR. TUCSON, AZ. 85701
PHONE: (520) 740-3731 FAX: (520) 243-4434

March 23, 2011

ADDENDUM NO. 6

PROJECT: Richey Blvd. Fuel Tank Replacement

SOLICITATION NO.: 1101396

TO ALL POTENTIAL BIDDERS:

Please be advised of the following additions, clarifications and/or changes which are hereby incorporated into the Bid Documents of the above referenced solicitation:

1. Addendum No. 6 prepared by M3 Engineering & Technology Corporation dated March 23, 2011 (3 Pages).

All other terms remain unchanged. This addendum is a total of 4 pages.

/s/ Melissa Hala'ufia

Melissa Hala'ufia, CPPB
Commodity/Contracts Officer

NOTE: Any bid that fails to acknowledge any addendum that directly affects cost, scope or schedule will be rejected as nonresponsive.

© 1996-2011
COMMERCIALITY
PROTECTED BY ELECTRONIC SIGNATURE TECHNOLOGY


**ADDENDUM NO. 6
TO CONSTRUCTION DRAWINGS & SPECIFICATIONS**

Pima County Facilities Management
150 West Congress, 5th Floor
Tucson, Arizona 85701

RE: Richey Blvd. Fuel Tank Replacement
Pima County P.O. No. 11002135

Dated: March 23, 2011

To All Bidders:



This addendum supplements and amends the original Specifications, dated December 17, 2010 and shall be taken into account in preparing proposals, and shall become part of the Contract Documents. In case of conflicts between the Specifications and this Addendum, the Addendum shall govern. Careful note of this Addendum shall be taken and all trades affected shall be fully advised for performance of the work. Acknowledge receipt of the Addendum in the space provided on the bid form. Failure to do so may subject bidder to disqualification.

Change reference in Addendum No. 4 on page 3 above 3.6 EXTERIOR PAINTING SCHEDULE from "Revise Section 15192 "FACILITY FUEL OIL PIPING"

To "Revise Section 09911 "EXTERIOR PAINTING."

NARRATIVE REVISION TO DRAWINGS:

CI001:

- 1. Revise Grading Note #10 to read: **"CONTRACTOR TO PROVIDE ENGINEER'S CERTIFICATION THAT THIS PROJECT WAS CONSTRUCTED IN SUBSTANTIAL CONFORMANCE WITH THE APPROVED PLANS PRIOR TO REQUEST FOR FINAL INSPECTION OR THE RELEASE OF ASSURANCES."**

Addendum No. 6
Pima County Facilities Management
P.O. No. 11002135
March 23, 2011

M3-PN100100

Page 2

NARRATIVE REVISION TO DRAWINGS (CONT.):

SJ501:

1. Revise Detail 'B' as follows: **Change 3/4" diameter weep hole to 2" PVC weep hole and slope in direction of drainage.**
2. Revise Section 'A' as follows: **Sealant to be placed at each end of slab joints, sealant per Spec Section 02764.**

SJ502:

1. Revise Detail '2' as follows: Add notes
 - a. **MOLDED RUBBER CONTROL JOINT SHALL BE A SHEAR LUG TYPE TO PROVIDE SHEAR CONTROL, MANUFACTURED OF HIGH GRADE SYNTHETIC RUBBER COMPOUNDS, BLENDED EPDM/SBR/CR TO MEET ASTM D-2000 AND MATERIAL STANDAR 80 HARDNESS - 500 PSI TENSILE.**
 - b. **SEALANT SHALL COMPLY WITH ASTM C 920, CLASS 25. SEALANT SHALL BE INSTALLED PER ASTM C962 AND PER MANUFACTURERS INSTALLATION INSTRUCTIONS. INSTALL WITH A BACKER ROD. SEALANT SHALL BE URETHANE BASED SYSTEM.**

MP101:

1. Revise Keynote No. 5 to read: **"NEW GASBOY DOUBLE HOSE, DUAL PRODUCT UNLEADED/DIESEL FUEL DISPENSER WITH DIGITAL DISPLAY AND ABOVE GROUND SECONDARY SPILL CONTAINMENT PLATFORM, MOUNT DISPENSER SO THAT (2) DISPENSER DISPLAY SCREENS FACE WEST AND (2) DISPENSER DISPLAY SCREENS FACE EAST, REFER TO SCHEDULE ON THIS SHEET FOR MORE INFORMATION."**

EG101:

1. Revise Keynote #11 as follows: **"CONTRACTOR SHALL VERIFY LOCATION OF EXISTING GROUND AND EXTEND NEW GROUND RING TO EXISTING SYSTEM GROUND, BONDING METHOD TO BE EXOTHERMIC."**

Addendum No. 6
Pima County Facilities Management
P.O. No. 11002135
March 23, 2011

M3-PN100100
Page 3

EP101:

1. Revise Keynote #8 as follows: **"EXISTING VEEDER ROOT LEAK DETECTION SYSTEM AND REQUIRED CABLES AND CONNECTIONS IN 3/4" CONDUIT TO NEW FUEL TANK TO BE REPLACED AND CONNECTED TO NEW PANEL 'GP.' VERIFY LOCATION AND CONNECTIONS WITH VENDOR. REFER TO DIAGRAM 3 SHEET 'EP501.'**
2. Change in plan Keynote reference #30 that points to south dispensers to #31.
3. Revise Keynote #29 as follows: **"NEW FE PETRO SYSTEM VERIFY FINAL CONNECTIONS WITH VENDOR PRIOR TO INSTALLATION."**

EP501:

1. On "INDOOR EQUIPMENT INSTALLATION DIAGRAM" detail 3 diagram, replace note that reads **"CONDUIT FOR CONNECTION OF COMMUNICATIONS BY PIMA COUNTY"** to read **"PROVIDE EMPTY CONDUIT FOR CONNECTION OF COMMUNICATIONS BY PIMA CO."**
2. On "INDOOR EQUIPMENT INSTALLATION DIAGRAM" detail 3, revise note #10 as follows: **"PROVIDE NEW VEEDER-ROOT RS232 BOARD, AND OUTPUT RELAY BOARD, PER PIMA COUNTY REQUIREMENTS."**

EP502:

1. Detail 1 "GROUNDING RING TEST WELL DETAIL" add note: **"DEPTH OF MAIN GROUND CONDUCTOR TO BE 36"**

END OF ADDENDUM NO. SIX